Serial No.	Items of work	Unit	Rate	Quantity	Cost
	Sluice No. 1 :—*R. L.* 45·00		Rs. a. p.		
1	Earth work cut opening the bund ..	Cyd.	0 3 6	38	8
2	Stone jelly concrete in surki mortar ...	C.ft.	0 4 6	113	32
3	Burnt brick in surki mortar ..	"	0 5 0	311	97
4	Burnt stone slabs 6" thick ..	S.ft.	0 5 0	112	35
5	Surki plastering ...	Sqr.	4 8 0	2	9
6	Providing cast iron pipe 5" dia including carting and jointing with cement complete.	R.ft.	2 0 0	36	72
7	Cutting holes in upper and lower orifice..	No.	1 0 0	3	3
	Providing plug and rod with locking arrangements.	Lump	sum	...	15
	Refilling with watering and tamping as per excavation.	Cyds.	0 3 6	39	8
	Total Sluice ...	..		...	279
	Sluice No. 2 :—				
	Same as per No. 1 sluice ...	...	...	...	279
	Waste Weir at R. L. 52·00—				
1	Approach draft clearing ...	Lump	sum	...	100
2	Excavating foundation ...	Cyd.	0 3 6	20	4
3	Concrete in surki ...	C.ft.	0 4 6	383	108
4	Burnt stone slabs ...	S.ft.	0 5 0	247	77
5	Plastering with surki mortar ...	Sqr.	4 8 0	4·37	8
6	Cutting Joggle joints ...	No.	0 12 0	11	8
	New stone work apron ...	Cyds.	1 10 0	39	63
	Total weir ...	...	...	...	449
	Total of Bund and Sluices and Weir—				
	= 3365 + 558 + 449 ...	....	...	..	4,372

C. T. NARASIMHA IYENGAR,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification, dated 9th March 1933.

Subject :—Constructing an Urdu Middle School Building at Kunigal.

The attention of the public is drawn to Notification calling for tenders for the above work in pages 319 and 320, Part VI of the *Mysore Gazette*, dated 23rd March 1933.

The tenders will be received by the Executive Engineer, Tumkur Division, Tumkur, up to 3 P.M. of 18th April 1933.

An earnest money of Rs. 350 should accompany the tender.

Notification, dated 28th March 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 3 P.M. of 26th April 1933, for opening a road from Gubbi to Chitnahalli (Chandrasekharapura) in Gubbi Taluk.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1934.

2. The plans, detailed estimates and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of Rs. 700 in cash or Currency Notes as earnest money and be superscribed "Tender for opening a road from Gubbi to Chitnahalli (Chandrasekharapur) in Gubbi Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimated amount will not be accepted.

10 No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In the matters of all disputes about rates and measurements quality of work, etc., and in all disputes of any kind, the decision of the Superintending Engineer will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lumpsum provisions are subject to modification as per data worked out during the execution. For individual items of work under lumpsum provisions the rates tendered for similar items of work will be paid and for other items, the rates as per schedule of rates will be paid at the discretion of the Executive Engineer.

Abstract estimate of quantities for opening a road from Gubbi to Chitnahalli (Chandrasekharapura) in Gubbi Taluk.

Sl. No	Details	Unit	Quantity	Rate	
				In figure	In words
	I. FORMATION OF ROAD.				
1	Clearing jungle	Furlong	82		
2	Removing stray boulders	C.yds.	120		
3	Earthwork, excavating drains in earth and gravelly soil and using the spoil for formation of road.	do	13,873		
4	Earthwork embankment where excavated stuff cannot be used.	L. S.	...		
5	Forming the road way including consolidation with rollers.	Miles	10¼		
6	Excavating and stacking gravel ...	C.yd.	5,610		
6(a)	Carriage for gravel half mile lead ...	do	5,610		
6(b)	Spreading forming and consolidating gravel	do	5,610		
7	Improving the existing cart track from Hindesgere to Chitnahalli. ...	Mile	1¾		
	II. CROSS DRAINAGE WORKS.				
1	Constructing causeways with wheel track slabs.	R.ft.	2,350		
	III. MISCELLANEOUS WORKS.				
1	Providing new finger posts complete as per new design.	Each	2		
2	Providing zero and mile stones (4½ x 1¼ x ½)	do	13		
3	Providing furlong stones (2¾ x 5/8 x ½) ...	do	84		
4	Providing land width stones (3 x ½ x ½) with dressing to a height of half foot.	...	386		
5	Providing new stone road rollers 3' x 2½' diameter with iron frames, etc., complete	do	3		

KADUR DIVISION.

Notification dated 16th March 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 17th April 1933, at 3 P.M., for "Constructing a new Middle School Building at Lakkavalli, Tarikere Taluk." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office, Chikmagalur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred and sixty (Rs. 160) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing a new Middle School Building at Lakkavalli, Tarikere Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be quoted for each and every item.

10. Percentage quotations either below the lowest tender or below the estimated rates will not be accepted.

11. In all matters of dispute regarding quality of work or rates, the decision of the Superintending Engineer, Shimoga Circle, Shimoga, is final and legally binding.

12. No claims of enchanced rates should be preferred after the acceptance of tender or at any time during execution of work.

13. For lumpsum items and also items found necessary during execution, rates as per current schedule rates or at tendered rates for such of the items as form a portion in lump-sum provision or as per rate, worked out and approved by the Superintending Engineer, Shimoga Circle, will be allowed.

14. No representations regarding rates, etc., from the rejected tenderers will be considered

15. The contractor shall hold himself responsible for good behaviour of his employees of all grades.

Abstract estimate for constructing a new Middle School Building at Lakkavalli, Tarikere Taluk.

No.	Items of work	Per	Quantity	Tendered rates	
				In figures	In words
1	Earthwork excavation, foundation and filling in basement.	C.yd.	147	Rs.	Rs.
2	Stone jelly concrete in mortar ..	C.ft.	1183		
3	Size stone in mud ...	"	2868		
4	Burnt brick in mud ...	"	4266		
5	Do in mortar ...	"	863		
6	Burnt stone slabs 6" thick dressed and fixed in mortar.	S.ft.	617		
7	Teakwood doors with panelled shutter, iron fittings, etc., complete.	"	172		
8	Teakwood windows with iron bars, panelled double half shutters, iron fittings, etc., complete.	"	180		
9	Teakwood wall shelves with panelled shutters and 1" thick planks, etc., complete.	"	96		
10	Teakwood 1½" feet diameter glazed circular ventilators.	Each	4		
11	Teakwood wrought and put including wood oiling, two coats.	C.ft.	210·81		

No.	Items of work	Per	Quantity	Tendered rates	
				In figures	In words
				Rs.	Rs,
12	Roofing with 1st class Mangalore tiles over teak reepers, etc., complete.	Sqr.	29·83		
13	Mangalore 1st class ridge tiles set in mortar and cement pointed.	R.ft.	116		
14	Cement pointing to basement ..	Sqr.	6·75		
15	Chunnam plastering	„	55·48		
16	White washing, two coats	„	55·48		
17	Flooring with 1st class Mangalore tiles over 3" concrete bed and cement pointing.	„	12·68		
18	Flooring with Kadapah slabs over 3" concrete bed and cement pointed.	„	4·56		
19	Chunam borders over roof ...	R.ft.	80		
20	Zinc sheets for valleys with teakwood 1" plank	S.ft.	207		
21	Chacolate painting two coats ..	Sqr.	10·55		
22	Bhadravathi painting to wood works ..	Lump	sum		
23	Teakwood eave boards 9" depth and $\frac{3}{4}$" thick ..	R.ft.	276		
24	Do finials (big) ...	No.	4		
25	Do small ...	„	10		
26	Teakwood sun shades to windows including chacolate painting, fixing, etc., complete.	Each	13		
27	Constructing a latrine as per type designs ..	..	..		
28	Teakwood pillars 6$\frac{1}{2}$ feet height 9" x 9" sqr. with capitals and stone base, etc., complete.	„	10		

L. A. H. WINCKLER,
Executive Engineer.

SHIMOGA DIVISION.

Notification No. 1395 *dated* 28*th March* 1933.

It is hereby notified for the information of the heirs of the undermentioned late Sub-overseers of the Shimoga Division and that if no claims are forthcoming with the necessary documents to establish their heirships within three months from the date of issue of this notification, the security deposits of these Sub-overseers will lapse to Government and that belated claims will receive no attention.

Names.	Amount under secarity deposit. Rs. a. p.
Mr. T. S. Vedhachalam Pillai	100 3 0
„ P. V. Veeraraghava Iyer	19 6 1

G. SESHAGIRI RAO,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

GOVERNMENT BOTANICAL GARDENS, LAL-BAGH, BANGALORE.

Notice dated 28*th March* 1933.

It is hereby notified that mango, rose, apple, jack, cocoanut and laquot crops will be sold by public auction at the Lal-bagh Office at 9-30 A.M. on Saturday 15th April 1933.

Terms of sale are as follows :—

1. Each bidder may be required on demand to deposit a sum of Rs. 10 as earnest money before he is permitted to bid, which amount will be returned to him at the close of the sale, if his bid be not accepted.

2. The highest bidder, who is the purchaser, should, on the spot, deposit 50 per cent of the amount due by him and pay up the balance within two days. In default thereof, the same will be resold at his risk without his participating in any profit that may accrue.

3. The removal of the same will not be permitted before full payment is made for the same.

4. All sales held by the subordinate officials in charge are subject to the confirmation of Superintendent, Government Gardens in Mysore, who reserves the right of accepting or rejecting any bid without assigning any reasons therefor.

4a. After the removal of the crop, the purchaser should tidy the place and any damage done should be made good by him.

5. In cases of complaints preferred by the purchaser, the decision of the Superintendent, Government Gardens, shall be final.